

TERREBONNE PARISH CONSOLIDATED GOVERNMENT

**BAYOU TERREBONNE DREDGING PROJECT
PHASE 2, 4 & 5
PARISH PROJECT NO. 21-DRA-10
DOTD PROJECT NO. H.009237**

ADDENDUM NO. 1

Date Issued: April 1, 2026

This Addendum No. 1 shall be part of the above referenced project.

Acknowledge receipt of this Addendum No. 1 by inserting its number in the space provided in the Louisiana Uniform Public Work Bid Form of the Request for Proposals. Failure to do so may subject the bidder to disqualification.



Kevan D. Keiser, P.E.
GIS Engineering, LLC

TERREBONNE PARISH CONSOLIDATED GOVERNMENT

BAYOU TERREBONNE DREDGING PROJECT

PHASE 2, 4, & 5

PARISH PROJECT NO. 21-DRA-10

DOTD PROJECT NO. H.009237

This Addendum is issued for the purpose of modifying, clarifying, or revising, as applicable, the specified items of the original Contract Documents. It is also issued for the purpose of adding, as applicable, the attached specified items to the original Contract Documents, or deleting, as applicable, the attached specified items from the original Contract Documents. The Addendum and attachments shall be construed as much a part of the original Contract Documents as contained therein. Changes made by Addenda shall take precedence over original Contract Documents.

GENERAL ANNOUNCEMENT

1. As per this Addendum, the Bid Opening has been rescheduled to Tuesday, April 14, 2026 at 2:00 P.M.
2. The deadline to submit questions to bidquestions@gisy.com has been extended to Tuesday, April 7, 2026 by 2:00 P.M.
3. In the case that additional questions have been received but are not answered in this addendum, these questions will be answered in a subsequent addendum to be issued on a later date.

PART I – WRITTEN CONTRACTORS QUESTIONS

PART II - MODIFICATIONS TO CONTRACT DOCUMENTS, TECHNICAL SPECIFICATION, PLANS, AND OTHER DOCUMENTS

Modifications to Contract Documents, Technical Specifications and Drawings.

PART III – ATTACHMENTS

1. Pre-Bid Meeting Notes & Sign-In Sheet
2. Section C – Louisiana Uniform Public Work Bid Form (Revised as per Addendum No. 1)
3. Technical Specification 204 – Temporary Erosion Control (Added as per Addendum No. 1)
4. Technical Specification 402 – Traffic Maintenance Surfacing (Added as per Addendum No. 1)
5. Plan Sheet G-05 – Disposal Site (Added as per Addendum No. 1)
6. Plan Sheet G-06 – Drawing Index (Added as per Addendum No. 1)
7. Geotechnical Report
8. CSV Point Files

PART I – Written Contractors’ Questions

NOTE – The responses presented in PART I may differ from those presented in the Pre-Bid Conference. The responses in PART I are current as of the date of this Addendum and if different supersede those provided at the Pre-Bid Conference or any previous addenda.

Contractors’ General Questions Received

1. Would it be possible for GIS to provide a .csv point file for the alignment P.I.’s as they are listed on the Plan Sheets 2-02, 4-02 and 5-06?

Response: Yes. The .csv files are included in Part III of this Addendum and also uploaded to the Central Bidding Website.

2. When was survey conducted?

Response: MPH conducted the utility survey in May of 2021. GIS Engineering’s survey department completed the topographic/bathymetric survey in March of 2021.

3. Will tree removal be at the contractor’s discretion?

Response: See sheet G-04 for guidance. All trees in the Bayou should be removed. Any limbs hanging in the path of the dredge equipment should be removed. Any trees on the bank line and/or sides of the bayou that are leaning over the bayou by 45 or more from vertical should be removed.

4. Are there any pre-approved access points, if so can you provide a list of these?

Response: All properties and bridges owned by Terrebonne Parish Consolidated Government will be approved for use as access points. Contractor will be required to coordinate with TPCG prior to using their property for use as an access points.

The Engineer is providing a list of access points used previously by the Geotech firm. Contractor must contact and coordinate with landowner prior to using those access locations.

5. Are all existing bulkheads to remain?

Response: Yes.

6. Clearing and Grubbing specification references root ball removals and compacted lift backfill of holes. Will this be required? Please advise further.

Response: Trees should be cut at the ground level. Root ball removal and filling of hole is not required for this project.

- 7. Dredging specification states that a tolerance of 6" above or below the prescribed grade will be permitted and paid as such. Plan sheet G-04 note 5, states that up to a one foot overcut is permitted, but at no direct pay. Will the contractor be paid for six inches of over excavation, but not beyond that? Will the contractor be required to dredge areas with only six inches of material above the prescribed grade?**

Response: Contractor will be paid for up to six inches of over excavation but not beyond that. Contractor will not be required to dredge areas with only 6 inches of material or less above the prescribed grade.

- 8. Can the owner/engineer provide potential access routes and landowners used on previous projects that may be options for this one?**

Response: See question 4. In previous projects, Contractors obtained their own agreements with landowners. TPCG allowed access from their properties and bridges.

- 9. Clearing and Grubbing specification states that clearing and grubbing will be measured by the linear foot, exclusive of gaps in the work. General note 36 states "Clearing & Snagging operations in all of phase 4 and in phase 5, sta. 570+00 to 899+00, will be minimal as the owner just completed a project to clear and snag trees, tree limbs, and debris from these areas. The bid quantities provided reflect the total linear foot distance along both sides of the Bayou. Should the contractor assume that this line item will not be paid in full? If this assumption is correct, can the engineer provide an estimate as to how much of this line item is expected to be performed and paid?"**

Response: Contractor should familiarize themselves with existing site conditions. The Owner just completed a clearing and snagging project in all of Phase 4 and from Sta. 570+00 to Sta. 899+00 in Phase 5. The clearing and snagging operations should be minimal in these areas as this was completed in 2025.

- 10. Please confirm that all landfill tipping fees for disposal at the Ashland Sanitary Landfill are the Contractor's responsibility and are included in the dredging unit prices. Additionally, please advise if current tipping fee rates will be provided by the Owner or if bidders should obtain them directly from the landfill.**

Response: Contractor shall dispose of all dredged earthen material at the Ashland Landfill. See Drawing G-05. All vegetation, merchantable timber, trees, debris, tires, foreign objects, etc shall become property of the Contractor. Contractor shall dispose of these materials according to all federal, state, and local rules and regulations. No fees shall be charged for disposing of dredged earthen material at the Ashland Landfill.

- 11. Please confirm if disposal of dredged material at facilities other than the Ashland Sanitary Landfill is permitted. If so, please identify the required approval process (e.g., Engineer approval, Owner approval, or a formal contract modification).**

Response: Only Ashland Landfill is permitted to receive the disposal and debris material. See question 10.

12. Can we use VRS-C4G for horizontal and vertical control?

Response: No.

13. Can we use multibeam for pre/process/as-built surveys?

Response: No.

14. Can we use LiDAR for the overbank surveys?

Response: No.

15. Will there be fees for disposal at Ashland Landfill?

Response: See question 10.

16. Will the contractor be responsible for handling the spoils at the landfill, or will the land fill handle the spoils? If the land fill handles the spoils how much can they take in a day?

Response: Yes. Contractor shall be required to provide equipment and labor to spread and grade the material at the landfill. Contractor shall not fill the drainage ditch at the disposal site and will be required to construct temporary silt fencing along the ditch. See sheet G-05.

17. Will the landfill be all weather accessible?

Response: Yes. However, the contractor will be responsible for maintaining the haul road by use of traffic maintenance surfacing. Contractor shall also be required to fix any ruts, damages, etc caused by disposal operations.

18. Are there contacts for landowners from previous contracts?

Response: See attached list.

19. How long can the contractor shut down highways 20 and 24 at one time?

Response: Contractor shall be required to coordinate all lane closures of state highways with DOTD. Contractor shall coordinate all bridge closures with the appropriate owner (DOTD or TPCG).

20. Can you give a good definition of what is cleared and grubbed tree size, leaner and etc.

Response: There are various tree types and sizes along the project. Contractor should familiarize themselves with the types of tree types and sizes to be cleared, snagged, removed, etc.

21. Does the contractor have to use the designated disposal area or another area could be used?

Response: Please refer to the response for Question No. 10.

PART II – Modifications to Contract Documents, Technical Specifications, Plans, and Other Documents

Contract Documents:

1. Section A – Advertisement for Bids

- a. Please revise the following paragraph to read as follows:

“Sealed bids will be received on ~~April 7, 2026~~, *April 14, 2026* by the Terrebonne Parish Consolidated Government (TPCG) Purchasing Division, at the 301 Plant Road, Houma, LA 70363 until 2:00 P.M as shown on the Purchasing Division Conference Room Clock, and TPCG shall at that time and place publicly open the bids and read them aloud.”

2. Section C – Louisiana Uniform Public Work Bid Form

- a. Please remove and replace with the revised Bid Form provided in Part III of this Addendum.

3. Section J – Special Provisions

- a. Please add the following paragraph:

“1.37 In the event that Terrebonne Parish suffers a hurricane, the disposal site at Ashland Landfill may be closed to disposals while handling hurricane debris operations.”

Technical Specifications:

1. Section 204 - Temporary Erosion Control

- a. Please add Section 204 -Temporary Erosion Control provided in Part III of this Addendum to the “Issued for Bid” specifications.

2. Section 402 – Traffic Maintenance Surfacing

- a. Please add Section 402 -Traffic Maintenance Surfacing provided in Part III of this Addendum to the “Issued for Bid” specifications.

Plans:

1. Plan Sheet G-05 – Disposal Site

- a. Please add Plan Sheet G-05 -Disposal Site provided in Part III of this Addendum to the “Issued for Bid” Set.

2. Plan Sheet G-06 – Drawing Index

- a. Please add Plan Sheet G-06 -Disposal Site provided in Part III of this Addendum to the “Issued for Bid” Set.

3. Plan Sheet 01 – Drawing Index

- a. Please remove from the “Issued for Bid” set.

PART III - ATTACHMENTS

Pre-Bid Conference Minutes & Sign-In Sheet



Date: March 19, 2026 at 10:00 A.M.

Project: Terrebonne Parish Consolidated Government
Bayou Terrebonne Dredging Project
Phases 2, 4, & 5
TPCG Project No. 21-DRA-10, DOTD Project No. H.009237
GIS Project No. 39130-1285

Location: GIS Engineering, LLC
197 Elysian Drive
Houma, LA 70363

**PRE-BID CONFERENCE
NOTES**

SAFETY TOPIC:

1. Roster Signatures and Introductions

- a. Owner – Terrebonne Parish Consolidated Government (TPCG)
- b. Engineer – GIS Engineering, LLC (GIS)

2. Scope of Work

The project consists of the dredging of Bayou Terrebonne from the Terrebonne/Lafourche Parish Line near Thibodaux, LA southward to an area just north of the Roy St Bridge near Bayou Cane, LA. The dredging will deepen Bayou Terrebonne to various elevations shown on the plan drawings. Fallen trees and debris are to be removed as well as the removal of trees on the bankline (leaners and hangers). All dredged material and tree/debris removal shall be hauled and disposed of at the Ashland Landfill in Terrebonne Parish, LA. Contractor shall also take pre-construction videos and photographs prior to commencement of dredging operations.

3. Delivery of Bids:

Sealed bids will be received on **Tuesday, April 7, 2026**, by the Terrebonne Parish Consolidated Government (TPCG) Purchasing Division, at the City of Houma Service Complex, 301 Plant Road, in Houma, Louisiana 70363 until **2:00 P.M** as shown on the Purchasing Division Conference Room Clock, and TPCG shall at that time and place publicly open the bids and read them aloud.

4. Proper Preparation and Submission of Bids (*Section 10.0 of Section B – Instruction to Bidders*)

- a. Bids to be submitted by the time and at place indicated in the Invitation to Bidders and shall be enclosed in a sealed envelope.
- b. Envelope shall include Project title and name, address and state license number of the Bidder.

- c. Each Bid Proposal packet shall include:
 - i. Completed Uniform Public Work Bid Form
 - ii. Signature Authorization with written evidence of authority (LA R.S. 38:2212(B)(5))
 - iii. Bid Bond with Power of Attorney, or Certified Check or Cashier's Check, all in the amount of 5% of the total amount of the bid.
 - iv. Completed Unit Price Form.

**Please be sure to fill in all spaces, including Unit Price Extension even if it's a Lump Sum Item*

5. Bid Completeness Requirements – including, but not limited to, the following:

- a. Acknowledgement of Addenda on Bid Proposal Form.
- b. Properly fill in unit price and extension price of each item included in the Bid Form.
- c. Complete bidder information as requested.
- d. Sign and Attest the bid.

6. Project Addenda:

- a. Clarifications in response to questions concerning Contract Documents will be issued in an Addendum.
- b. Send all questions to BidQuestions@gisy.com. Any questions submitted outside of this provided email address will not be considered. – **Please be sure to add the project name to the subject line.**
- c. Addenda will be issued as soon as possible, but no later than **Wednesday, April 1, 2026 before 2:00 P.M.** Addenda will be available at <http://www.centralbidding.com> by clicking on the Project Link, and will also be sent via email provided on the sign-in sheet for this meeting.

7. Contract Documents and Requirements:

- a. Listed in Section F – Standard Form of Agreement Between Owner and Contractor
- b. Contract Documents include complete Plan, Specifications, Addenda and Reference Documents.

8. General Project Information:

- a. Contract Time: 365 Calendar Days from Notice to Proceed.
- b. Estimated Project Budget: \$8,000,000.00
- c. Required Contractor's License: Heavy Construction, and/or Dredging
- d. Liquidated Damages: \$1,500.00 per day. Refer to Section B, Instruction to Bidders, Section F – Contract and Section I – General Conditions
- e. Contractor's Liability Insurance: Please refer to Section F, 9.2 and Paragraph 5.4 of Section I – General Conditions for requirements.
- f. There will be mandatory monthly progress meetings with Engineer and Owner personnel during construction.

9. Special Provisions Highlights

- a. 1.09 – Load Limits – transportation of equipment and hauling of spoil for disposal
- b. 1.12 – Protection of roadway surfaces...any damage must be repaired and must keep clean
- c. 1.13 – Coordination with DOTD and TPCG if any road or lane closures are required
- d. 1.14 – Work in high traffic area and multiple school zones
- e. 1.15 – Maintenance of drainage
- f. 1.16 – Communication – Must have someone available to take calls at all times
- g. 1.17 – Must provide sanitation facilities for employees and project representatives
- h. 1.18 – Inspector's Field Office requirements
- i. 1.19 – Tax Exemption – exempt from State Sales tax
- j. 1.20 – Insurance is required and will not be measured for payment (See also Section I of General Provisions)

- k. 1.21 – Submit construction schedule upon award of contract and must submit updated schedule monthly along with Pay Apps
- l. 1.25 – Contractor shall be required to coordinate all ROW and easement access with various landowners
- m. 1.26 – Hurricane Preparedness Plan
- n. 1.28 – Comply with all federal, state, and local regulations for dredging, removal of materials, and hauling to landfill (Ashland Landfill)
- o. 1.29 – Suspension of Work for Non-Compliance
- p. 1.30 – Contractor to coordinate with all utility/pipeline crossings
- q. 1.32 – Cleaning of debris/mud from vehicles and roads
- r. 1.36 – All agencies and their representatives shall have access to project site throughout the duration of the project

10. Agency/Owner Comments

***Any bridge/road closures should be coordinated with TPCG.**

11. Bid Questions & Responses

- a. Questions received prior to this pre-bid conference will be addressed in an upcoming addendum within the following days.
- b. All future questions shall be in writing and sent to the email address BidQuestions@gisy.com. We will not accept any questions over the phone or sent to direct emails.
- c. The last day to submit written questions will be **Monday, March 30, 2026 before 2:00 P.M.**

12. Site Familiarity

- a. Interested contractors should familiarize themselves with the project site, conditions, and challenges prior to bidding. There will not be an official pre-bid site visit.

13. Adjourn

Project Contact Information

GIS Engineering, LLC

Kevan Keiser
BJ Robichaux
TBD
Ann Schouest

985-219-1000

Engineer of Record/Project Manager
Construction Manager
Resident Project Representative
Project Associate



Terrebonne Parish Consolidated Government
 Bayou Terrebonne Dredging Project
 Phases 2, 4, & 5
 TPCG Project No. 21-DRA-10
 DOTD Project No. H.009237
 Thursday, March 19, 2026
 10:00 A.M.



ATTENDANCE REGISTER

NAME	COMPANY NAME	PHYSICAL ADDRESS	TELEPHONE NUMBER	EMAIL ADDRESS
1 MADELEINE BODIN	TPCG	8026 MAIN ST	985-873-6720	mbodin@tpcg.org
2 Lenwick Harding	TPCG	8026 MAIN ST	985-8736718	lharding@tpcg.org
3 TOMMY CRASBY	DYNAMIC	3045 WESTFORK Dr. BATON ROUGE	(504) 415-0083	tcrasby@dynamicgrp.com
4 Blake Wells	Michels Construction Inc.	817 Main Street Brantsville, WI 53006	(985) 258-1238	BLWells@Michels.us
5 Trae Eschette	Onshore Materials, LLC	127 Lincoln Lane Thibodaux, LA 70301	985-449-0391 985-449-0391	trae@onshoreco.com
6 B.J. Robichaux	GISY	197 Elysian Ave Houma, La 70363	985-688-4101	brobichaux@gisy.com
7 Kent Gravois	Lowland	Houma LA 70363	504 329 4328	Kent@lowlandci.com
8 Quentin Landry	LA Contracting Enterprise	1645 St. Patrick St. Thibodaux, LA 70301	985-446-2212	bidding@la-cont.com
9 Ann Schouest	GIS Engineering, LLC	197 Elysian Drive Houma, LA 70363	985-219-1001	aschouest@gisy.com
10 KEVAN KEISER	GIS ENGINEERING, LLC	" " "	985-219-1000	kkeiser@gisy.com

PART III - ATTACHMENTS

Section C

Louisiana Uniform Public Work Bid Form

SECTION C
LOUISIANA UNIFORM PUBLIC WORK BID FORM

TO: Terrebonne Parish Consolidated Government
City of Houma Service Complex
301 Plant Road
Houma, LA 70363
(Owner to provide name and address of owner)

BID FOR: Bayou Terrebonne Dredging
Phases 2, 4, & 5
Project No. 21-DRA-10
DOTD Proj. No. H.009237
(Owner to provide name of project and other identifying information)

The undersigned bidder hereby declares and represents that she/he; a) has carefully examined and understands the Bidding Documents, b) has not received, relied on, or based his bid on any verbal instructions contrary to the Bidding Documents or any addenda, c) has personally inspected and is familiar with the project site, and hereby proposes to provide all labor, materials, tools, appliances and facilities as required to perform, in a workmanlike manner, all work and services for the construction and completion of the referenced project, all in strict accordance with the Bidding Documents prepared by: GIS Engineering, LLC and dated: March 2026
(Owner to provide name of entity preparing bidding documents.)

Bidders must acknowledge all addenda. The Bidder acknowledges receipt of the following **ADDENDA:** (Enter the number the Designer has assigned to each of the addenda that the Bidder is acknowledging) _____ .

TOTAL BASE BID: For all work required by the Bidding Documents (including any and all unit prices designated “Base Bid” * but not alternates) the sum of:
_____ Dollars (\$ _____)

ALTERNATES: For any and all work required by the Bidding Documents for Alternates including any and all unit prices designated as alternates in the unit price description.

Alternate No. 1 *(Owner to provide description of alternate and state whether add or deduct)* for the lump sum of:
_____ N/A _____ Dollars (\$ _____ N/A _____)

Alternate No. 2 *(Owner to provide description of alternate and state whether add or deduct)* for the lump sum of:
_____ N/A _____ Dollars (\$ _____ N/A _____)

Alternate No. 3 *(Owner to provide description of alternate and state whether add or deduct)* for the lump sum of:
_____ N/A _____ Dollars (\$ _____ N/A _____)

NAME OF BIDDER: _____

ADDRESS OF BIDDER: _____

LOUISIANA CONTRACTOR’S LICENSE NUMBER: _____

NAME OF AUTHORIZED SIGNATORY OF BIDDER: _____

TITLE OF AUTHORIZED SIGNATORY OF BIDDER: _____

SIGNATURE OF AUTHORIZED SIGNATORY OF BIDDER **: _____

DATE: _____

THE FOLLOWING ITEMS ARE TO BE INCLUDED WITH THE SUBMISSION OF THIS LOUISIANA UNIFORM PUBLIC WORK BID FORM:

- * The Unit Price Form shall be used if the contract includes unit prices. Otherwise it is not required and need not be included with the form. The number of unit prices that may be included is not limited and additional sheets may be included if needed.
- ** **A CORPORATE RESOLUTION OR WRITTEN EVIDENCE** of the authority of the person signing the bid for the public work as prescribed by LA R.S. 38:2212(B)(5).

BID SECURITY in the form of a bid bond, certified check or cashier’s check as prescribed by LA RS 38:2218(A) attached to and made a part of this bid.

SECTION C
LOUISIANA UNIFORM PUBLIC WORK BID FORM
UNIT PRICE FORM

TO: Terrebonne Parish Consolidated Government
City of Houma Service Complex
301 Plant Road
Houma, LA 70363
(Owner to provide name and address of owner)

BID FOR: Bayou Terrebonne Dredging
Phases 2, 4, & 5
Project No. 21-DRA-10

(Owner to provide name of project and other identifying information)

UNIT PRICES: This form shall be used for any and all work required by the Bidding Documents and described as unit prices. Amounts shall be stated in figures and only in figures.

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Mobilization and Demobilization			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
727-01	1	LUMP SUM		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Mechanical Dredging (Phase 2: Sta. 10+67 to Sta. 84+50; includes hauling and disposal of dredged material at landfill)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
312300-01	1,288	CUBIC YARDS		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Mechanical Dredging (Phase 4: Sta. 400+00 to Sta. 486+50; includes hauling and disposal of dredged material at landfill)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
312300-02	21,896	CUBIC YARDS		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Mechanical Dredging (Phase 5: Sta. 500+00 to Sta. 899+00; includes hauling and disposal of dredged material at landfill)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
312300-03	49,290	CUBIC YARDS		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Clearing & Grubbing (Phase 2: Sta. 10+67 to Sta. 122+00; includes hauling and disposal of material at landfill)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
201-01	22,266	LINEAR FEET		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Clearing & Grubbing (Phase 4: Sta. 400+00 to Sta. 486+50; includes hauling and disposal of material at landfill)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
201-02	17,300	LINEAR FEET		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Clearing & Grubbing (Phase 5: Sta. 500+00 to Sta. 899+00; includes hauling and disposal of material at landfill)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
201-03	79,800	LINEAR FEET		

Wording for "DESCRIPTION" is to be provided by the Owner. All quantities are estimated. The contractor will be paid based upon actual quantities as verified by the Owner

SECTION C
LOUISIANA UNIFORM PUBLIC WORK BID FORM
UNIT PRICE FORM

TO: Terrebonne Parish Consolidated Government
City of Houma Service Complex
301 Plant Road
Houma, LA 70363
(Owner to provide name and address of owner)

BID FOR: Bayou Terrebonne Dredging
Phases 2, 4, & 5
Project No. 21-DRA-10
(Owner to provide name of project and other identifying information)

UNIT PRICES: This form shall be used for any and all work required by the Bidding Documents and described as unit prices. Amounts shall be stated in figures and only in figures.

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Removal of Structures and Obstructions (Phase 2: Sta. 10+67 to Sta. 122+00; includes hauling and disposing at landfill)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
202-01	1	LUMP SUM		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Removal of Structures and Obstructions (Phase 4: Sta. 400+00 to Sta. 486+50; includes hauling and disposing at landfill)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
202-02	1	LUMP SUM		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Removal of Structures and Obstructions (Phase 5: Sta. 500+00 to Sta. 899+00; includes hauling and disposing at landfill)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
202-03	1	LUMP SUM		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Removal of Trees Leaners & Hangers (Phase 2: Sta. 10+67 to Sta. 122+00; includes hauling and disposing at landfill)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
201-04	1	LUMP SUM		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Removal of Trees Leaners & Hangers (Phase 5: Sta. 500+00 to Sta. 570+00; includes hauling and disposing at landfill)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
201-05	1	LUMP SUM		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Construction Layout (Phase 2)_____			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
740-01	1	LUMP SUM		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Construction Layout (Phase 4)_____			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
740-02	1	LUMP SUM		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Construction Layout (Phase 5)_____			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
740-03	1	LUMP SUM		

Wording for "DESCRIPTION" is to be provided by the Owner. All quantities are estimated. The contractor will be paid based upon actual quantities as verified by the Owner

SECTION C
LOUISIANA UNIFORM PUBLIC WORK BID FORM
UNIT PRICE FORM

TO: Terrebonne Parish Consolidated Government
City of Houma Service Complex
301 Plant Road
Houma, LA 70363
(Owner to provide name and address of owner)

BID FOR: Bayou Terrebonne Dredging
Phases 2, 4, & 5
Project No. 21-DRA-10
(Owner to provide name of project and other identifying information)

UNIT PRICES: This form shall be used for any and all work required by the Bidding Documents and described as unit prices. Amounts shall be stated in figures and only in figures.

DESCRIPTION: <input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Pre-Construction Survey (Phase 2)				
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
013200-01	1	LUMP SUM		

DESCRIPTION: <input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Pre-Construction Survey (Phase 4)				
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
013200-02	1	LUMP SUM		

DESCRIPTION: <input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Pre-Construction Survey (Phase 5)				
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
013200-03	1	LUMP SUM		

DESCRIPTION: <input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Pre-Construction Video Recording (Phase 2)				
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
S001-01	1	LUMP SUM		

DESCRIPTION: <input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Pre-Construction Video Recording (Phase 4)				
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
S001-02	1	LUMP SUM		

DESCRIPTION: <input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Pre-Construction Video Recording (Phase 5)				
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
S001-03	1	LUMP SUM		

DESCRIPTION: <input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Utility/Pipeline Oversight and Coordination				
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
740-04	1	LUMP SUM		

DESCRIPTION: <input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Temporary Signs and Barricades				
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
713-01	1	LUMP SUM		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Temporary Silt Retention System (Silt Fencing)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
204-06	2,400	LINEAR FOOT		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Traffic Maintenance Surfacing (610 Limestone)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
402-03-01	1,500	TON		

DESCRIPTION:	<input checked="" type="checkbox"/> Base Bid or <input type="checkbox"/> Alt.# <u>N/A</u> Traffic Maintenance Surfacing (3 x 1 Limestone)			
REF. NO.	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (<i>Quantity times Unit Price</i>)
402-03-02	500	TONS		

Wording for “DESCRIPTION” is to be provided by the Owner. All quantities are estimated. The contractor will be paid based upon actual quantities as verified by the Owner

PART III - ATTACHMENTS

Technical Specification 204

Temporary Erosion Control



**BAYOU TERREBONNE DREDGING
PROJECT (PHASES 2, 4, &5)
TECHNICAL SPECIFICATIONS
TEMPORARY EROSION CONTROL
SECTION NO. 204**



TABLE OF CONTENTS

1.0	GENERAL	1
1.1	Description	1
2.0	CONTROL OF ERODIBLE SOIL	Error! Bookmark not defined.
2.1	General	1
2.2	Materials – Silt Retention System.....	1
3.0	EXECUTION	1
3.1	Construction Requirements	1
3.2	Maintenance of Erosion Control Features	1
3.3	Removal of Temporary Erosion Control Features	1
4.0	MEASUREMENT AND PAYMENT	1
4.1	Measurement	1
4.2	Payment	2



**BAYOU TERREBONNE DREDGING
PROJECT (PHASES 2, 4, &5)
TECHNICAL SPECIFICATIONS
TEMPORARY EROSION CONTROL
SECTION NO. 204**



1.0 GENERAL

1.1 Description

This work consists of constructing and maintaining temporary erosion control features as shown on plans or as directed.

2.0 CONTROL OF ERODIBLE SOIL

2.1 General

Prevent the transmission of soil particles into streams, canals, lakes, reservoirs, ditches, or other waterways. Except as necessary for construction, do not deposit excavated material into streams or impoundments or in a position close enough to be washed into the waterways by water runoff.

Do not disturb lands or waters outside the limits of construction, except as authorized.

2.2 Materials – Silt Retention System

Silt fencing shall be wire-supported and shall comply with Section 1018.15 of the LADOTD Standard Specifications for Roads and Bridges, latest edition.

3.0 EXECUTION

3.1 Construction Requirements

Furnish and construct silt fencing at designated locations as directed by the engineer. Posts for silt fencing shall be installed to a depth necessary to maintain the integrity of the system.

3.2 Maintenance of Erosion Control Features:

Inspect silt fencing at least once every 14 calendar days and within 24 hours after a rainfall event of 0.5 inches or greater. Document these inspections and maintain records in field office and provide to the Engineer for review. Repair and maintain fencing prior to disposal of materials.

3.3 Removal of Temporary Erosion Control Features:

Remove and dispose of silt fencing at the end of the project.

4.0 MEASUREMENT AND PAYMENT

4.1 Measurement

Measurement of temporary silt retention systems (silt fencing) shall be taken along the ground surface using linear feet.



**BAYOU TERREBONNE DREDGING
PROJECT (PHASES 2, 4, &5)
TECHNICAL SPECIFICATIONS
TEMPORARY EROSION CONTROL
SECTION NO. 204**



4.2 Payment

Payment for temporary silt retention systems (silt fencing) will be made at the contract unit price.

Payment will be made under:

Item Number	Pay Item	Pay Unit
204-06	Temporary Silt Retention System (Silt Fencing)	Linear Foot

-END OF SECTION-

PART III - ATTACHMENTS
Technical Section 402
Traffic Maintenance Surfacing



**BAYOU TERREBONNE DREDGING
PROJECT (PHASES 2, 4, &5)
TECHNICAL SPECIFICATIONS
TRAFFIC MAINTENANCE SURFACING
SECTION NO. 402**



TABLE OF CONTENTS

1.0	GENERAL	1
1.1	Description	1
2.0	CONTROL OF ERODIBLE SOIL	Error! Bookmark not defined.
2.1	General	1
2.2	Materials – Silt Retention System.....	1
3.0	EXECUTION	1
3.1	Construction Requirements	1
3.2	Maintenance of Erosion Control Features	1
3.3	Removal of Temporary Erosion Control Features	1
4.0	MEASUREMENT AND PAYMENT	1
4.1	Measurement	1
4.2	Payment	1



**BAYOU TERREBONNE DREDGING
PROJECT (PHASES 2, 4, &5)
TECHNICAL SPECIFICATIONS
TRAFFIC MAINTENANCE SURFACING
SECTION NO. 402**



1.0 GENERAL

1.1 Description

Furnish and construct surfacing for maintenance of traffic on driveways, pipe crossings, short-term traffic on raw embankment, slope corrections, or other disturbed roadway sections as directed and in accordance with the following requirements.

2.0 MATERIALS

2.1 General

Furnish the following types of materials as directed by the Engineer.

610 Limestone	1003.01 & 1003.05.1
3x1 Limestone	1003.01 & 1003.05.1

2.2 Equipment

Furnish and maintain equipment necessary to produce a finished product meeting the requirements of these specifications. Obtain approval of equipment prior to use.

3.0 EXECUTION

3.1 Construction Requirements

Satisfactorily place, shape, compact, and maintain areas require traffic maintenance surfacing. When directed, reuse the aggregate material at adjacent locations when the material can reasonably be shifted by blading. When directed, material shall be loaded, hauled, and reused.

4.0 MEASUREMENT AND PAYMENT

4.1 Measurement

Aggregate used for traffic maintenance surfacing will be measured at the point of delivery by the ton in approved hauling vehicles in accordance with 109.01. No adjustment factor will be used.

4.2 Payment

Payment for traffic maintenance surfacing, maintained, will be made at the contract unit price per ton. Aggregate materials reused by blading to adjacent locations will be at no expense to the Owner.

Payment will be made under:

Item Number	Pay Item	Pay Unit
402-03-01	Traffic Maintenance Surfacing (610 Limestone)	Ton
402-03-02	Traffic Maintenance Surfacing (3x1 Limestone)	Ton

-END OF SECTION-

PART III - ATTACHMENTS
Plan Sheet G-05 – Disposal Site
Plan Sheet G-06 – Drawing Index

PART III - ATTACHMENTS

Geotechnical Report

Bayou Terrebonne Dredging - Geotechnical Report

PART III - ATTACHMENTS

.CSV Point Files

200	412847.9	3463470	0 seg2
201	412657.9	3463552	0 seg2
202	412498.1	3463624	0 seg2
203	412298.2	3463719	0 seg2
204	412173.2	3463796	0 seg2
205	412092	3463846	0 seg2
206	411972.5	3463922	0 seg2
207	411889.8	3463963	0 seg2
208	411672.8	3464102	0 seg2
209	411605.2	3464147	0 seg2
210	411346.6	3464345	0 seg2
211	411255	3464410	0 seg2
212	411105.4	3464532	0 seg2
213	410973.8	3464634	0 seg2
214	410868.3	3464721	0 seg2
215	410669.7	3464860	0 seg2
216	410530.7	3464975	0 seg2
217	410446.9	3465040	0 seg2
218	410196.3	3465252	0 seg2
219	410134.4	3465306	0 seg2
220	410057.3	3465359	0 seg2
221	409924.5	3465446	0 seg2
222	409674.4	3465617	0 seg2
223	409561.2	3465693	0 seg2
224	409434.3	3465781	0 seg2
225	409230.6	3465921	0 seg2
226	409011.8	3466054	0 seg2
227	408932.6	3466111	0 seg2
228	408851.1	3466171	0 seg2
229	408760.2	3466226	0 seg2
230	408674.7	3466285	0 seg2
231	408573.9	3466358	0 seg2
232	408483.3	3466407	0 seg2
233	408392.4	3466476	0 seg2
234	408231.1	3466564	0 seg2
235	408046.7	3466669	0 seg2
236	407873.1	3466761	0 seg2
237	407697.8	3466859	0 seg2
238	407486.5	3466972	0 seg2
239	407355.8	3467041	0 seg2
240	407292.2	3467057	0 seg2
241	407121.2	3467121	0 seg2
242	406932.7	3467214	0 seg2
243	406545	3467368	0 seg2

244	406471	3467403	0 seg2
245	406320.6	3467458	0 seg2
246	405994.4	3467568	0 seg2
247	405463.7	3467715	0 seg2
248	405125.1	3467808	0 seg2
249	405048.3	3467835	0 seg2
250	404887.9	3467867	0 seg2
251	404683.8	3467905	0 seg2
252	404636.7	3467920	0 seg2
253	404263.8	3467964	0 seg2
254	404080.4	3467995	0 seg2
255	403950.7	3468000	0 seg2
256	403874.1	3468018	0 seg2
257	403818.2	3468026	0 seg2
258	403709	3468053	0 seg2
259	403498	3468098	0 seg2
260	403429.1	3468110	0 seg2
261	403312.6	3468139	0 seg2
262	403118.6	3468203	0 seg2
263	402921.8	3468284	0 seg2

400	427761.2	3456756	0 seg4
401	427574.4	3456908	0 seg4
402	427434.8	3457064	0 seg4
403	427298.1	3457189	0 seg4
404	427147.1	3457331	0 seg4
405	427005.1	3457468	0 seg4
406	426879.5	3457586	0 seg4
407	426816.8	3457639	0 seg4
408	426691.7	3457708	0 seg4
409	426614.9	3457759	0 seg4
410	426528.7	3457829	0 seg4
411	426357.1	3457941	0 seg4
412	426178.2	3458041	0 seg4
413	426024.2	3458140	0 seg4
414	425844.1	3458246	0 seg4
415	425796	3458279	0 seg4
416	425684.7	3458341	0 seg4
417	425501.3	3458444	0 seg4
418	425367.5	3458513	0 seg4
419	425134.4	3458617	0 seg4
420	424939.9	3458699	0 seg4
421	424780.2	3458772	0 seg4
422	424608.5	3458845	0 seg4
423	424394.9	3458938	0 seg4
424	424188.2	3459019	0 seg4
425	424019.1	3459087	0 seg4
426	423833.3	3459148	0 seg4
427	423668.2	3459189	0 seg4
428	423518.8	3459264	0 seg4
429	423466.2	3459298	0 seg4
430	423295	3459380	0 seg4
431	423195.1	3459436	0 seg4
432	423127.4	3459478	0 seg4
433	422938.1	3459576	0 seg4
434	422759.9	3459673	0 seg4
435	422596.5	3459766	0 seg4
436	422403.6	3459865	0 seg4
437	422231.5	3459957	0 seg4
438	422169.5	3459999	0 seg4
439	422056.2	3460066	0 seg4
440	422034	3460076	0 seg4
441	421857.6	3460172	0 seg4
442	421718.9	3460267	0 seg4
443	421572.2	3460335	0 seg4

444	421511	3460366	0 seg4
445	421365	3460468	0 seg4
446	421205.5	3460559	0 seg4
447	421144.9	3460594	0 seg4
448	421036.9	3460663	0 seg4
449	420869.6	3460757	0 seg4
450	420685.9	3460865	0 seg4
451	420574.4	3460918	0 seg4
452	420516.9	3460944	0 seg4
453	420475.7	3460967	0 seg4
454	420343.6	3461038	0 seg4
455	420324.5	3461047	0 seg4

500	463769.6	3444835	0 seg5
501	463558.6	3444924	0 seg5
502	463350.4	3444968	0 seg5
503	462970.5	3445039	0 seg5
504	462875.2	3445049	0 seg5
505	462803.2	3445064	0 seg5
506	462757.8	3445074	0 seg5
507	462674.5	3445084	0 seg5
508	462574.9	3445087	0 seg5
509	462385	3445086	0 seg5
510	462309.4	3445087	0 seg5
511	462216.5	3445092	0 seg5
512	461972	3445091	0 seg5
513	461853.6	3445084	0 seg5
514	461769	3445083	0 seg5
515	461236.6	3445089	0 seg5
516	461043.1	3445093	0 seg5
517	460776.4	3445091	0 seg5
518	460591.3	3445104	0 seg5
519	460415.5	3445118	0 seg5
520	460266.9	3445119	0 seg5
521	460179.7	3445116	0 seg5
522	459986.8	3445095	0 seg5
523	459779.1	3445084	0 seg5
524	459457.8	3445049	0 seg5
525	459304.6	3445031	0 seg5
526	459194.1	3445009	0 seg5
527	458946.3	3444971	0 seg5
528	458704.6	3444940	0 seg5
529	458682.6	3444955	0 seg5
530	458651.5	3445077	0 seg5
531	458628.1	3445091	0 seg5
532	458598.3	3445085	0 seg5
533	458107.1	3444927	0 seg5
534	457918.1	3444875	0 seg5
535	457731.2	3444843	0 seg5
536	457539.7	3444827	0 seg5
537	457330.9	3444820	0 seg5
538	457015.7	3444803	0 seg5
539	456926.2	3444808	0 seg5
540	456727.6	3444829	0 seg5
541	456601	3444852	0 seg5
542	456492.4	3444881	0 seg5
543	456351.5	3444930	0 seg5

544	456124.5	3445036	0 seg5
545	456059.8	3445016	0 seg5
546	455987.9	3444890	0 seg5
547	455955.8	3444880	0 seg5
548	455873.3	3444918	0 seg5
549	455235.4	3445399	0 seg5
550	455071.3	3445470	0 seg5
551	454857.8	3445526	0 seg5
552	454697.2	3445552	0 seg5
553	454466.1	3445626	0 seg5
554	454283.2	3445699	0 seg5
555	454091.4	3445789	0 seg5
556	453377.2	3446128	0 seg5
557	453337.6	3446231	0 seg5
558	453433.1	3446461	0 seg5
559	453370	3446697	0 seg5
560	453198.1	3446829	0 seg5
561	453141.3	3446869	0 seg5
562	452603.4	3447250	0 seg5
563	452479.5	3447312	0 seg5
564	452375.7	3447334	0 seg5
565	452301.2	3447329	0 seg5
566	452044.4	3447269	0 seg5
567	451877.8	3447305	0 seg5
568	451678.5	3447456	0 seg5
569	451496.2	3447631	0 seg5
570	451098.3	3448096	0 seg5
571	450910.2	3448253	0 seg5
572	450699.2	3448447	0 seg5
573	450552.4	3448565	0 seg5
574	450437.7	3448644	0 seg5
575	450229	3448781	0 seg5
576	449862.4	3449009	0 seg5
577	449623	3449097	0 seg5
578	449527.4	3449110	0 seg5
579	448888.7	3449286	0 seg5
580	448652.5	3449329	0 seg5
581	448365.7	3449359	0 seg5
582	447692.6	3449470	0 seg5
583	447071.3	3449582	0 seg5
584	446554.8	3449713	0 seg5
585	446158.2	3449844	0 seg5
586	445409.5	3450137	0 seg5
587	444867.8	3450358	0 seg5

588	443634.9	3450948	0 seg5
589	443543.3	3450991	0 seg5
590	442778.4	3451444	0 seg5
591	441867	3451919	0 seg5
592	441784.9	3451962	0 seg5
593	441673.7	3452015	0 seg5
594	441359.4	3452202	0 seg5
595	441150.4	3452289	0 seg5
596	440717.1	3452485	0 seg5
597	440586.4	3452524	0 seg5
598	439759	3452836	0 seg5
599	439458.6	3452955	0 seg5
600	439061.4	3453097	0 seg5
601	438893	3453139	0 seg5
602	438285.1	3453363	0 seg5
603	438185.5	3453400	0 seg5
604	437864.7	3453530	0 seg5
605	437474.6	3453708	0 seg5
606	437054	3453900	0 seg5
607	436833.2	3453971	0 seg5
608	436506.3	3454101	0 seg5
609	436153.4	3454203	0 seg5
610	435990.3	3454261	0 seg5
611	435881.6	3454289	0 seg5
612	435718.7	3454353	0 seg5
613	435537.7	3454455	0 seg5
614	435357.8	3454525	0 seg5
615	435152.4	3454575	0 seg5
616	434983	3454610	0 seg5
617	434854.9	3454635	0 seg5
618	434655.3	3454687	0 seg5
619	434046.5	3454735	0 seg5
620	433365.3	3454786	0 seg5
621	433071.6	3454793	0 seg5
622	432552.3	3454770	0 seg5
623	432360.7	3454781	0 seg5
624	432046.6	3454820	0 seg5
625	431817.6	3454862	0 seg5
626	431172.5	3454937	0 seg5
627	430998.1	3454970	0 seg5
628	430660.2	3455055	0 seg5
629	430162	3455166	0 seg5
630	429600.1	3455360	0 seg5
631	429338.7	3455468	0 seg5

632	429166.3	3455591	0 seg5
633	428842	3455801	0 seg5
634	428626.2	3455995	0 seg5
635	428041.7	3456480	0 seg5
636	427795.9	3456730	0 seg5
637	427641.8	3456844	0 seg5